TUMKUR DIVISION.

Dated 26th October 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 27th November 1933, for restoring the breached Gowdihalli tank, Registered No. 328 of Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4 Each tender must be accompanied by a deposit of rupees two hundred (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring breached Gowdihalli Tank Registered No. 328 of Tumkur Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the Bond for any short progress or delay. In matters of all disputes about rates and measurements and quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work. Lumpsum provisions are subject to modification as per data worked out during execution. For individual items of work under lumpsum provision, the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be at the discretion of the Executive Engineer

Abstract of quantities for restoring the breached Gowdihalli tank, Re. No. 328 of Tumkur Taluk.

Serial No.	Items of work	Per	Quantity	Rate in words and figures
	Bund R. L. 56·00 Top Width 4½ feet.			
1	Clearing jungle and removing ant hills ...	Grade	26	
2	Cutting grips to bund	L. S.	...	
3	Earthwork to bund including watering, tamping, etc., complete.	C.yds.	8752	
4	Earthwork for breached portion to be done with selected earth, well watered, etc. ...	„	454	
5	Excavating foundation to the puddle wall and cutting slopes to the breach.	L. S.	..	
6	Puddle wall	C.yd.	140	
7	Turfing the slopes of bund	Syd.	9500	
8	Rough stone pitching with old stones ...	C.yd.	49	
9	Old rough stone work for revetment with new jelly	„	75	
10	Fixing new grade with index stones ...	Each	26	
11	Do B.M. Stones ...	„	2	
12	Do Register No. stones ...	„	1	
	II. Sluice No. I. R. L. 44·00.			
1	Earthwork cutting bund and refilling with consolidation.	C.yd.	96	

Serial No.	Items of work	Per	Quantity	Rate in words and figures
4	Burnt stone slabs	S.ft.	162	
5	Plastering with surki mortar	Sqr.	4 20	
6	Cutting orifice holes in slabs	Each	4	
7	Providing plug with rod complete with locking arrangements.	L. S.	..	
	III. Sluice No. II R.L. 44·00 as per above.			
	IV. Waste weir left 140' long.			
1	Earthwork (chargeable to bund) excavation for foundation.	C.yds.	128	
2	Concrete in surki mortar	C.ft.	730	
3	Burnt brick in surki mortar	"	719	
4	Burnt stone slabs dressed and fixed	S.ft.	30	
5	Plastering with surki mortar	Sqr.	13·68	
6	Rough stone work for apron old stones to be removed and carted to site.	C.yd.	82	
	V. Waste Weir Right 100' Long			
1	Earthwork (chargeable to bund) excavation for foundation.	C.yd.	93	
2	Concrete in surki mortar	C.ft.	540	
3	Burnt brick in surki mortar	"	585	
4	Burnt stone slabs dressed and fixed.... ..	S.ft.	30	
5	Plastering with surki mortar	Sqr.	10·68	
6	Rough stone work for apron old stones to be removed and carted to site.	C.yd.	62	

Dated 26th October 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M., on 27th November 1933, for restoring Besige-Doddakere, Registered No. 88 of Tiptur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 300 (three hundred) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Besige-Doddakere, Registered No. 88 of Tiptur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rate above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance of tenders.

11. The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rates and measurements and quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and egally binding on the contractor.

12. Rates should be quoted both in words and in figures for each item of work. Lumpsum provisions are subject to modification as per data worked out during execution. For individual items of work under lumpsum provision, the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be at the discretion of the Executive Engineer.

Abstract estimate of quantities for restoring Besige-Doddakere, Registered. No. 88 of Tiptur Taluk.

Sl. No.	Items of work	Per	Quantity	Rate in words and figures
	I Bund R. L. 55·50.			Rs. a. p.
1	Clearing jungle	L. S.	..	
2	Cutting grips to receive fresh earth	,,	...	
3	Earthwork to bund including lead, lift, watering for mixing, etc., complete.	C.yd.	13,495	
4	Turfing the slopes of bund, ...	Syd.	10,537	
5	Providing and fixing grade with index stones including figures cut and painted.	Each	42	
6	Providing and fixing B. M. stones with figures cut and painted.	,,	2	
7	Do do Register No. stone ...	,,	1	
8	New rough stone work to bund ..	Cyd.	349	
9	Removing and resetting the existing old apron ...	,,	250	
	II Sluice R. L. 42·00.			
	Cut opening the bund and refilling after repairing the existing sluice.	L. S.	..	
	III Waste Wair R. L. 50·00.			
1	Earthwork excavating for foundation ...	Cyd.	80	
2	Concrete in surki mortar ...	Cft.	690	
3	Burnt brick in surki mortar ...	,,	1,152	
4	Burnt stone slabs (6") ...	Sft.	24	
5	Plastering with surki mortar ...	Sqr.	17·43	
6	Clearing draft and approaches ..	L. S.	...	

N. G. KRISHNA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification dated 19th October 1933.

The attention of the public is invited to the detailed notification of 19th October 1933 regarding the sale of an old P. W. D. Sub-Division Office building at Hunsur, published on page 1339 of Part VI of the *Mysore Gazette*, dated the 26th October 1933.

V. V. PATANKAR,
Executive Engineer.

ARASALU-ANANDAPURAM RAILWAY CONSTRUCTION DIVISION, SHIMOGA.

Abstract Notification, dated 28th October 1933.

Attention of intending contractors is invited to this office notification, dated 21st October 1933, published in pages 1340 and 1341, Part VI, of the *Mysore Gazette*, dated 26th October 1933, for collecting broken stone ballast on Arasalu-Anandapuram Railway.

Last date for receiving tenders is 10th November 1933 (4-P.M.)

A. VISWANATH,
Executive Engineer.